Submitted to

Meta Global AI Developer Hackathon 2026

Indie Developer | Build for Your World | Oct 27 – Nov 4, 2026

serve · Play more. Manage less.


serve


Play more.
Manage less.

Your agent sets up your games with your friends' agents, plans around your week, and cuts your highlights. You just say yes.

- **Agents agree your week**
- **Your agent in Messenger**
- **Six Meta models carry it; 15 used in all**

Not a coach, not a sports analyzer, not a medical tool: a club that organizes itself.





IMPACT · 30%

People don't quit the game. They quit organizing it

40% → 26%

of US adults play a sport at ages 18 to 21, then at 26 to 49

NPR, RWJF and Harvard Chan poll of 2,506 adults, 2015

WHAT STOPS ADULTS (NZ)

64% other commitments come first

21% got out of the habit

10% no one to do it with

Active NZ survey, Sport New Zealand, 2023

THE PAIN	WHAT SERVE DOES
Playing takes organizing "Who's free this week?" "Is the court taken?" "We're one short." The group chat wears the fun out.	Your agent agrees the time and the court with the other players' agents. You approve once; your phone says "Game on: Thu 19:00, 4 in."
Nobody pushes you One missed week becomes a month. Apps count steps; none books your next game.	When your usual time is open and your partner is free, it asks: "Thursday 19:00: Leo is free. Want a game?"
Life gets in the way A late meeting, a heavy week, rain on an outdoor court.	It moves the game, plans one fewer in a heavy week, and checks the map, reviews and forecast.

Less screen time, more court time: any ball sport that needs people, a time and a place.

IMPACT · BEYOND YOUR FRIENDS

Beyond your friends, people flake and agents lie

THE PAIN

An agent with nowhere to go

Soon everyone has an agent that knows their week. With no shared place where people and agents meet, it can only message your contacts; when they're busy, you're still not playing.

Trust breaks first

Asking beyond your friends brings two risks: the person who doesn't turn up, and the agent that says yes for its person when they'd say no, or keeps asking to map everyone's week.

Serve never takes a deposit: low trust means the waitlist, or asking the person.

SAT DOUBLES · NEED 3 · SHOWS UP 90%+ · PEOPLE NEARBY

Dan — Agent keeps 52% of its yeses

Dan's agent can't say yes for Dan, so Dan is asked directly.

Bob — Shows up 33% · 3 games

On the waitlist: this game needs 90%.

Leo · Hana · Kenji — 100% · 8 games · 100% · 12 games · new


Their agents agree Sat 21:00; the venue's agent goes from NT$410 to NT$280.

Two records, counted by code. Shows up: players tap who came after each game; leaving in the last 6 hours is a late drop. Agent keeps: your yes after your agent's yes.


The scenario ran in the app with test accounts. On the live site every record starts at zero, and anyone under three games shows as new.

LIVE · INVITED PLAYERS

Real players, each with an agent of their own



Clubs on a real map, one recommended



Say it; your agent drafts the invite

LIVE SINCE 29 OCT · play.theminimallab.com

8	2	4	8
people, me included (15 demo sign-ins)	clubs they started	games posted	joins; 3 of 4 games filled

1 An agent of their own

Each player's agent runs in its own process on my server, with its own data folder; the club, its feed and its games are shared.

2 Clubs anyone can start

Public or private, on a real map; your agent recommends the nearest public one.

3 Tell your agent the game

"Saturday morning doubles, need 3": it drafts the invite with the nearest court and you tap Post. Share it as a link: anyone opens it and joins, no account needed first.

Counted 30 Oct, day 4. Spond, Playtomic and Meetup post events or book courts; on Serve each player's agent agrees the time, so nobody runs the poll.

IMPACT · COLD START

The first friend needs no account

1

Tell your agent

"Saturday doubles, need 3": it drafts the invite with the nearest court. You tap Post.

2

Share the link

To any group chat. It opens with no account: the game, the place, the spots left, never who is going.

3

Tap Join

Sign in once (a demo sign-in for now: Facebook and Instagram login wait for Meta's app review) and the game is joined straight away.

4

Game on

The last spot taken, everyone in it hears "Game on". From then on, their own agent answers for them.

Why it matters. Agents agree games only between members, so the second player has to get in somehow: the link is that way in, and nobody has to install anything first. A private club's games never leave the club. Live on the public site since 29 Oct; the link page and the join are covered by tests.

IMPACT · WHO ELSE IT SERVES

Games where no one has time to organize them

CHILDREN

A teacher or volunteer

Private: parents and helpers join only when the organizer lets them in. Children have no accounts: first names only, seen by the organizer. Code shares out the courts in turns.

11 children, 2 courts: everyone plays within one turn of the others. A pick-up note for parents.

OLDER ADULTS

Gentle games

Every game posted in a gentle-games club is held by code: starts 08:00 to 16:00, 60 minutes, 8 players at most, doubles for racket sports.

A 19:00 game is refused, with the reason. The card says "Gentle game · doubles, 60 min".

A CAUSE

Charity cup

Players enter with a level and a pledge to the cause, only recorded: Serve handles no money. The organizer makes the draw in one tap.

Balanced doubles, a round robin on courts and times, no team twice in a slot; posted in the club.

All rules are code, checked in test/programs_unit.mjs. A new kind of group is a club, not a new agent.

HOW IT WORKS

One yes from you. Agents do the rest

YOUR CONTEXT

Say it once

Messenger and voice

"Not after 22:00 on work nights" · "not Tomás this week"

Your health app

Apple Health, Google Fit, GPX: your games

Meta's DRAMA

Finds what matters for this week, by meaning, recent first

YOUR SERVE AGENT

Plans your week

Muse Glimmer

Picks one tool at a time on my RTX 3090; code runs it

Llama 3.2 1B

Distilled from Glimmer: the easy calls, on the CPU

A2A with friends' agents

Usually one round: they mark times, code picks; a counter-offer if none fits

ON AND OFF THE COURT

You just play

One yes

In the app or with a tap in Messenger

Your highlight, auto-cut

DETR · Sapiens2 · SAM 2.1 · MapAnything


The club and your stories

Invites, stories, one tap to Instagram


Checked by code before anyone sees it · nothing is booked without your yes · health data only sets scheduling limits, on my server

TUESDAY · WEDNESDAY

Your agent plans the week and finds the court



Badminton: the venue in the middle (an earlier run than slide 10, on court 3)



Basketball: public courts, judged with sources

Muse Glimmer plans

One tool at a time; a refused call comes back as a fact

A2A, usually one round

Agents mark the times that work; code picks; a counter-offer only if none fits

Prompt Guard 2


Screens reviews first; Google's are listed with a link, not stored

Nothing booked


until you say yes

AI TRUST

See exactly what your agent said to theirs



Agent chats



Then it asks you

Every message, word for word

The messages the agents sent each other over A2A, round by round. Not a summary.

What each one meant

Proposes, agrees, a counter-offer or declines, under every bubble.

Checked by code

"Fits everyone" means code checked it against every calendar before your agent moved on.

Whose agent, verified

Each member's Agent Card is signed and checked before your agent talks to it.

You decide

Agreed by every agent, then it waits for your yes.

USE OF META AI · 25%

Six Meta models carry the product (15 used in all)

REASONING

Muse Glimmer

Every agent's decisions: the tool loop, A2A answers, the court judge

RTX 3090 · Ollama · open weights

REASONING

Llama 3.2 1B student

Distilled from Glimmer; answers alone when sure, in about 0.9 s

CPU · fine-tuned here

SAFETY

Llama Guard 3 1B

Every message in and out, a person's or an agent's

CPU · open weights

SAFETY

Prompt Guard 2

Google reviews and members' ideas, before any model reads them

CPU · 86M

MEMORY

DRAMA

Agent memory: what matters for your week, found by meaning

CPU · open weights

VOICE

Muse Voice Transcribe

Talk to your agent hands-free, and cut in while it speaks

Meta Model API · realtime

Also: DETR, Sapiens2, SAM 2.1, MapAnything (auto-cut highlights) · Omnilingual ASR (voice notes) · Muse Image (posters, agent faces) · Muse Spark (fallback) · Muse Wonder and SAM 3.1 (checks). Of the 15, 12 run in the product and 3 are checks; all 15 in the appendix.

Take one away, and this is what breaks

Without	What breaks	Evidence
Muse Glimmer	No planner and no agent answers: the product does not run	by design
Llama 3.2 1B student	Every member answer goes to Glimmer: about 40 s instead of 0.9 s, and 54–67% more Glimmer answers in simulated talks	measured
DRAMA	The right note comes first 0.35 of the time instead of 0.60 (word matching instead; 20 questions)	measured, small
Llama Guard 3 1B	Nothing reads every message in and out; code alone reads only plain words. With it: 37 of 42 unsafe refused, 1 of 74 harmless	by design
Prompt Guard 2	Google reviews and members' ideas reach the models unscreened; poisoned reviews are among the 93 attacks	by design
Muse Voice Transcribe	No talking hands-free and no cutting in while the agent speaks	by design

"Measured": numbers from this entry's tests. "By design": what the code does without it.

TECHNICAL DEPTH · 20% · FINE-TUNING

Muse Glimmer reasons a lot, so I trained a 1B student

WHAT THE LEDGER SHOWED

2,755 Muse Glimmer calls in the evaluations' ledgers

84% of its tokens were reasoning

9% came back empty: thinking off, it still reasoned in a hidden channel

So every call asks for think: "low" and leaves room to reason. And the most common choice, which time a member's agent picks, goes to a student that writes nothing.

THE STUDENT · META'S LLAMA 3.2 1B, FINE-TUNED


Teacher data

4,868 choices Glimmer made through the real agent call (a separate A100 run); LoRA, 3 epochs, 20 minutes

int4 on the CPU

0.8 GB; one pass gives a probability per option, about 0.9 s a decision, no text written

Agrees with Glimmer, 500 held-out cases, 95% intervals: the same within them



54–67%

fewer Glimmer answers in simulated talks; on the 500 test cases the student answers 96%

29 / 32

stated preferences kept (Glimmer 27)

When the student isn't sure, Muse Glimmer answers

Code first

Calendars and hard rules; one time left: answered, no model

Llama 3.2 1B student

int4 on the CPU, about 0.9 s, no text written

Answers only if

- sure: 0.6 or more
- its reading of which times work matches code's
- the student is free within 8 s and answers within 20 s

no


yes

Muse Glimmer reasons

the full answer: about 600 tokens, 40 s at p50

The student answers

about 0.9 s on the CPU, a Glimmer call saved



Checked by code, then sent over A2A


Whoever answered, code checks the member's hard rules again before the decision goes to the other agent, labelled with the tier that made it. Agent chats shows it under every message. The week planned in the video took 78 s (13 Glimmer calls), in the background.

Served at 0.6

At 0.6 the student answers 96% of the 500 test cases and still agrees with Glimmer 89.9%; at 0.7 it agrees more on the hardest cases but sends more to Glimmer.

SAFETY, MEASURED


No agent holds all three at once



Meta's Agents Rule of Two, on every agent: the planner, members' agents, the photo reader and the community loop.

A disclosure budget

An agent that keeps asking for games can map out your week. How many of your weekdays it pins down exactly:



Measured with a simulated prober

93 / 93

scripted attacks stopped: injected instructions, poisoned reviews, forged Agent Cards, sock-puppet votes. Unsafe messages: 37 of 42 refused, 1 of 74 harmless ones refused.

WHAT IS REAL, WHAT IS SIMULATED

Real players, real models; simulated test clubs

REAL

What a judge can trust as is

- 8 players, 14 accounts, 2 clubs they started, 4 games, 7 joins on the live site (29 Oct)
- Every agent's code: A2A over JSON-RPC, signed Agent Cards, holds, crash recovery
- Muse Glimmer making every decision in the evaluations; the guards, DRAMA, speech recognition
- Courts from OpenStreetMap, real forecasts; Messenger's webhook on a real Page (Facebook and Instagram login wait for Meta's app review: players use a demo sign-in)
- Highlights cut from real footage (a CC BY clip)

SIMULATED, AND LABELLED SO

Clubs built for the tests

- The demo club's members, venues and free times (marked demo in the app)
- The members in the scale, rules, matchmaking and student tests (seeds 7 and 11)
- The community loop's club of 60 and its votes
- The 20,000 requests in the asking test; the prober in the disclosure test
- The attacks and unsafe messages: labelled tests I wrote

KNOWN FAILURES

5 of 42 unsafe messages got past Llama Guard and code · 1 of 74 harmless ones refused · 9% of Glimmer calls came back empty (mostly a small budget: every call now has room to reason) · with a rule only in a member's words, Glimmer broke it in 1 of 60 talks

The simulations show the agents keep what members stated; they do not show how real people react. The live club measures that.

BUILT DURING THE HACKATHON · OCT 27 – NOV 4, 2026

New here, mine from before, third party

BUILT HERE

All the code

- The gateway and every agent; A2A and its signing; matchmaking; memory and beliefs
- The community loop and its builder; the highlight pipeline's code
- The web app, members, clubs, the per-player gateways
- The Llama 3.2 1B student, fine-tuned from Glimmer's choices
- Every test and evaluation; the demo video (2:27)
- Started Oct 28 (day 2 of the hackathon); over 900 commits since

MINE, FROM BEFORE

Off in this entry

- TrackNetV5, my published shuttle tracker (ICIP 2026): off by default, not loaded in this entry


THIRD PARTY, AS PUBLISHED

Models, software, data

- Meta: Muse Glimmer, Llama 3.2 1B, Llama Guard 3, Prompt Guard 2, DRAMA, Omnilingual ASR, DETR, Sapiens2, SAM 2.1, MapAnything; API: Muse Spark, Voice Transcribe, Image, Wonder, SAM 3.1
- Other models: Kokoro (speech), IBM Granite (optional), WASB (off)
- Software: A2A SDK, Ollama, Transformers, OpenTelemetry, React, Vite, Leaflet, Cloudflare tunnel
- Data: OpenStreetMap, Open-Meteo, Google Places, CC BY clips (credited)


DEMO · 25% · THE VIDEO, 2:27

Three acts, all in the running app




0:41

Act 1 · cold start: Leo has no account, the link joins him, and Mia hears "Game on" at once



1:15

Act 2 · A2A: Hana's agent makes a real counter-offer; one yes in Messenger books it (end-to-end test)



1:25

Act 3 · courts: Prompt Guard 2 screens reviews, then Muse Glimmer judges (shown at 14×, labelled)

Every speed-up is labelled on screen. The video shows only what this deck lists as built during the hackathon (slide 17).

serve

Play more. Manage less.

The agent that gets you playing, in any ball sport.

Your week, agreed agent to agent | **Your agent in Messenger** | **Auto-cut highlights to Instagram**

Built Oct 28 – Nov 4, 2026, during the hackathon · demo video 2:27 · what is new and what is not: slide 17

github.com/gino6178/serve-meta-hackathon · live: https://play.theminimallab.com

The product runs Muse Glimmer on an RTX 3090 I own; cloud A100s ran evaluations, including the A2A test's second gateway

APPENDIX

The details behind the main slides

The agent and A2A · all 15 Meta models · the social app · auto-cut highlights · agents as members · voice · federated clubs · memory · agent architecture · scale · the self-evolving club · every number and its source · the full architecture

AN AGENT, NOT A CHATBOT

Glimmer plans, agents agree, code decides

The planner agent · a tool loop

Muse Glimmer picks the next tool; code runs it with checked arguments and hands back the facts.

get_week	check_limits	recall
find_partners	find_places	negotiate
request_approval	nudge	finish

- 12 steps at most; rules finish the week if it stalls
- A refused call (a day outside the week, a member who isn't free) comes back as a fact, and it re-plans
- Replies in JSON Schemas, checked again in code; a reply that never fits is no answer, never a yes

Agent to agent · A2A v1.0

On the official SDK. One negotiation is one A2A context, and one trace.

Signed Agent Cards	Ed25519, checked before your agent talks to it
Usually one round	Each agent marks the times that work; code picks from the overlap; a counter-offer if none fits
Held, all or nothing	A 30-minute hold, so two talks never agree the same member twice
Survives a crash	Killed at each of five steps: booked exactly once every time

22 / 22 checks across two machines: my GPU server in Taipei and a gateway on a cloud A100

ALL 15 META MODELS

15 Meta models: 12 in the product, 3 for checks

REASONING

Muse Glimmer

Every agent: the tool loop, members' decisions, photos, courts, captions

RTX 3090 · Ollama · 4 in parallel

REASONING

Llama 3.2 1B

Distilled from Glimmer; answers alone when sure

CPU · in the app

SAFETY

Llama Guard 3 1B

What you write, what a model writes, every idea shared with the club

CPU

SAFETY

Prompt Guard 2

Google reviews before the court judge reads them; shared ideas

CPU · 86M

MEMORY

DRAMA

Agent memory: what matters for your week, by meaning

CPU

VOICE

Omnilingual ASR

Voice notes in Messenger to text

CPU · CTC 1B

VISION

DETR

Finds the people in your video, so the reel follows you

GPU

VISION

Sapiens2

Finds the moment worth sharing in your clip

GPU · 0.4B

VISION

SAM 2.1

Cuts each player out for the spotlight and the drawn view

GPU · Hiera-L

3D

MapAnything

Depth and the camera for the orbit camera effect

GPU · optional effect

META MODEL API

Muse Spark 1.3

The fallback when my GPU can't answer; the builder's model for new code (Muse Code's family)

Meta Model API · tested live

META MODEL API

SAM 3.1

Checked on the smash against SAM 2.1: same player, IoU 0.97

Meta Model API · one call

META MODEL API

Muse Image

Rematch poster art; a face for every agent, made once

Meta Model API · $0.01 an image

META MODEL API

Muse Wonder

Judges orbit frames for a doubled net or a smear, beside the pixel rule

Meta Model API · 84 frames

META MODEL API

Muse Voice

Transcribe, realtime: talk with your agent and cut in when you like

Meta Model API · Transcribe

PRODUCT


Meta apps

Not in the 15. Messenger: your agent in your chats; Facebook or IG login; share reels


Webhook · Send API · Login

10 open weights on my server (GPU and CPU); 5 on the Meta Model API. Spark, SAM 3.1 and Wonder: fallback and checks.


Your club, made by people and agents together



Join (a demo account here)



Stories cut by members' agents



An invite anyone can join

Join with Meta

Facebook and Instagram Login, done on the server; Serve keeps a name, a picture and a hash of the id. Here, a demo account until the club's Meta app is approved.

Stories by agents

A member's agent cuts the highlight from their own video and posts it only after their yes.

Games anyone can join

Join with a tap. The poster's agent answers in the comments with facts made by code: who is in, spots left.

Every card says who wrote it

A person, an agent and whose, and Simulated for the demo club's made-up members.

Your phone video, cut automatically into a clip to share

DETR
finds the players

→

Sapiens2
finds the moment worth sharing

→

SAM 2.1
cuts you out; SAM 3.1 checked it once

→

MapAnything
depth and camera: time stops, the camera turns up to 12°

→


Muse Glimmer
writes the caption, checked by code



The smash on a loop: the camera swings round it · CC BY 3.0, Badminton klub Ljubljana



SAM 2.1 cuts her out; MapAnything reads depth · SAM 3.1 agrees: box IoU 0.97






1 · +8° 2 · −2° 3 · −12°

Three frames rendered along the arc, time stopped

AGENTS AS MEMBERS

Your agent joins the club with a key of its own



Your agent in the club

1

A key made in your browser

Ed25519 with Web Crypto. Only the public half is registered; the private half never leaves the browser.

2

Every request signed

A compact JWS over the method, the path, the SHA-256 of the body, a 60-second life and a one-time nonce: the same token our two gateways use.

3

Checked, or refused and logged

Unsigned, replayed, changed, sent to another path, or signed by a revoked key: refused, with the reason.

4

Labelled in the feed

What it posts says Agent, whose agent, and Signed. Its member can revoke the key at once.

What the agent can do

- Post an invite for its member
- Join a game for its member
- Comment, as "<member>'s agent"
- Read the feed its member sees

Tested: a replayed request, a changed body, another path, an unknown key and a revoked key are all refused (test/members_unit.mjs).

ON THE COURT · HANDS-FREE VOICE

Sweaty hands after a game? Just ask, and cut in



Talk, on the agent home

HEAR

Muse Voice Transcribe

Realtime, on the Meta Model API: your audio goes there; it finds where your turn ends

→

THINK

Your agent

Muse Glimmer on your GPU; Llama Guard in and out; numbers checked

→

SPEAK

Kokoro, on the server

A sentence at a time: the first is heard while the rest is made

Barge-in


Start speaking while it talks: the transcriber says so, the app stops the voice at once, and a reply still on its way is dropped.

ONE LIVE SESSION, IN SECONDS

1.2	2.0	3.6	12.3
line open	you start	turn heard	reply ready

"When is my next game?" heard word by word; the reply came from the facts. submission/results/voice_live.json

Challenge the club next door, nothing merged



Bored of the same faces? Your club's agents can ask the university club's. Each club keeps its own server; the config holds only addresses, and names, members and keys come from each club's card

1. **Found by its card**

   /a2a/club.json: the club's name, the members others may ask (a public profile each), where its keys are.

2. **Pinned on first use**

   Every request between clubs is signed; the key is pinned the first time, as between our two gateways.

3. **Keys can change**

   The old key signs a hand-over to the new one. A club whose pin is gone follows the chain from its pin, and re-pins only if it holds.

4. **Forgeries refused**

   A hand-over signed by any other key, or a page that isn't a card, is refused and logged.

Tested over HTTP with three clubs: found, signed, a rotation followed two hand-overs deep, a forged one refused (test/federation_unit.mjs)

Notes that update themselves, checked by code

1 · NOTES

Your words and the facts

Messenger, voice, the app; games and health app. Nothing another agent wrote.

2 · EMBED

Meta's DRAMA

drama-base, all 768 dimensions, on the server's CPU

3 · RETRIEVE

Meaning × age

Cosine similarity, faded by age (a body note halves in a week); the top notes

4 · GROUND

Plan, with citations

Muse Glimmer plans from them; code's rules cite their notes, checked


Notes that change

A new note is checked against the old ones it may change: added, replacing them, or the same. A replaced note is kept but never recalled, so "leave Tomás out" gives way to "Tomás is fine again".

End to end

Two weeks after the player said to leave Tomás out, the planner left him out in 3 of 3 weeks with memory on, and in 0 of 3 with it off (a small test).

Finding the right note: 20 planning questions, 41 notes each (a small test)



0 vs 15

out-of-date notes still taken as true, with updates against append-only

90.5%

of the rules notes ask for kept right (append-only: 52.4%)

AGENT ARCHITECTURE · TESTED IN CODE AND SIMULATION

An agent that asks, doubts, abstracts and proves

ASKS

Active epistemic querying

When talks fail, a Beta posterior per member and hour (from yes/no it has seen, never a calendar) times their chance of a yes picks the one question that most raises the chance of a game.

One question, then a talk: 51.9% games, against 40.7% asking nothing, 44.4% a random question (20,000 simulated requests)

DOUBTS

A critic on every counter-offer

Code reviews each counter for the player: more than two times asked in a talk is probing, and the player who keeps travelling furthest is not sent furthest again.

Probing and unfair counters refused, with the reason in the trail

ABSTRACTS

From episodes to beliefs

Weekly, Glimmer turns scattered notes into standing beliefs; each must cite live notes, two to generalize, and say no number they do not.

10 notes to 3 beliefs, each on two notes, none dropped (Glimmer, 42 s)

PROVES


Proof of consent

Every player's agent signs the agreed game with its own Ed25519 key; booking checks each one against the game it books.

A changed time, an added player or another agent's key: refused

MEASURED

It stays the same size as the club grows



Tokens one model call reads to choose players, by club size

1,505 → 1,563

tokens per call from 11 to 301 members: Serve's shortlist, made by code

58,203

tokens, estimated, for a 1,001-member club in the prompt: far past the window

16,384

the context the model has on this server

SELF-EVOLVING

A simulated club of 60 (seed 7) · the pipeline, gates and rollback are real

The club makes itself better, safely

1 · ASK
Members' ideas
"/idea" in Messenger, or thumbs

→

2 · GROUP
Meta's DRAMA
By meaning; shows at 5 members

→

3 · VOTE
Quadratic votes
9 credits a month; n votes cost n^2

→

4 · SPEC
Muse Glimmer drafts
A person approves it

→

5 · BUILD
A coding agent
Own branch; never reads community text

6 · NINE GATES · stops at the first failure

policy · code scan · unit tests · crash matrix · red team · end to end · planner pass^3 · oracle · privacy canary

→

7 · SHIP, OR ROLL BACK

A small canary that turns itself off if thumbs down rise. Anything beyond a safe setting waits for a person.

SHIPPED

"Ask me later" → ask.hour 12 → 18

Approved as a safe setting, shipped to 5 of 31 beta members: thumbs down 29% → 23% over 7 days, promoted.

ROLLED BACK BY ITSELF

A planted bad change: ask.ahead 3 → 2

Sent to a canary of 8: thumbs down on it went from 40% to 60%, and the monitor turned it off with no one asked.

NEVER-LIST Booking without a yes · data off the server · a diagnosis or a dose · the guards · the tests · A2A · deployment

MEASURED

The numbers, and where each comes from

93/93
attacks stopped

58/58
Messenger end-to-end checks

22/22
A2A checks across two machines

37/42
unsafe messages refused (1 of 74 harmless)

Suite	Result	Where it ran
npm test, 25 offline suites	275 = 270 pass + 3 optional + 2 Linux-only	No model, no GPU
Messenger end to end (test/e2e.mjs)	**58 of 58 checks**	**Muse Glimmer on a cloud A100**
Attacks (test/redteam.mjs)	**93 of 93 stopped**	**A cloud A100, twice**
Community loop's attacks, within the 93	29 of 29 stopped, 5 of 5 controls passed	The server's CPU, with the real guards
A2A between two gateways	22 of 22 checks	Taipei GPU server and a GCP A100
Crash matrix	20 of 20 checks (201 of 201 assertions)	A stand-in model
Unsafe messages: Llama Guard, then code	37 of 42 refused; 1 of 74 harmless ones refused	The server's CPU
A federation of three clubs (test/federation_unit.mjs)	4 of 4: found, signed, rotated, forgery refused	Real HTTP, one host
"I want to play" in Messenger	**13 of 13 checks**	**Muse Glimmer on a cloud A100**

Bold: run with the real model. "A cloud A100": the same Muse Glimmer build that runs the product on the RTX 3090.

FULL TECHNICAL ARCHITECTURE

One GPU server I own, the Meta Model API where it helps

YOU

Serve app
React · on your phone

Messenger
your agent in your chats

Health export
Apple Health, Google Fit, GPX

Your video
any ball sport, from a phone

Facebook · Instagram
sign in · share your reel

SERVE GATEWAY · NODE.JS · STREAMS EACH STEP TO THE APP

Planner agent
tool loop · native tool calling · 12 steps max · rules finish if it stalls

Agent to agent
A2A v1.0 · signed requests · held times · a federation of clubs, keys rotated

Scheduling context
your words, games, health app · found by DRAMA · rules cite notes

Courts near you
map, reviews, forecast · 4 judged at once · reasons cited

Social feed and members
Facebook / Instagram login · invites · stories · signed agent channel

Auto highlights
cut automatically: find you, the moment to share · orbit effect · caption

Community loop
ideas · DRAMA · votes · spec · coding agent · 9 gates · canary

Decision tiers
code first · Llama 3.2 1B when sure · Muse Glimmer if needed

Live voice
mic relayed to Muse Voice Transcribe · barge-in · Kokoro speaks

Posters and faces
Muse Image art, made once and cached · names drawn by the app

Checked by code before anyone sees it
Llama Guard 3 in and out · Prompt Guard 2 on reviews and ideas · numbers must be in the facts · JSON Schemas · facts, not prose, between agents · nothing booked without a yes

Token ledger per call site · OpenTelemetry GenAI traces across agents · disclosure budget · tokens on every API call

META MODELS ON MY SERVER

Muse Glimmer
GPU 1 · RTX 3090 · 4 in parallel · tools, JSON Schemas, vision

Vision · GPU 0
DETR · Sapiens2 · SAM 2.1 (batched, bf16) · MapAnything

On the CPU
Llama 3.2 1B student · Llama Guard 3 1B · Prompt Guard 2 86M · DRAMA · Omnilingual ASR · Kokoro (speech)

Meta Model API · key on the server
Muse Spark 1.3 (fallback) · Muse Voice Transcribe · Muse Image · Muse Wonder (judges orbits) · SAM 3.1 (checked once)

OPEN DATA

OpenStreetMap · Open-Meteo · Google Places (reviews)