Submitted to

# Meta Global AI Developer Hackathon 2026

Indie Developer | Build for Your World | Oct 27 – Nov 4, 2026

serve · Play more. Manage less.


serve


# Play more.
# Manage less.

Your agent sets up your games with your friends' agents, plans around your week, and cuts your highlights. You just say yes.

- **Agents agree your week**
- **Your agent in Messenger**
- **Six Meta models carry it; 15 used in all**

Not a coach, not a sports analyzer, not a medical tool: a club that organizes itself.



IMPACT · 30%

# People don't quit the game. They quit organizing it

## 40% → 26%

of US adults play a sport at ages 18 to 21, then at 26 to 49

NPR, RWJF and Harvard Chan poll of 2,506 adults, 2015

### WHAT STOPS ADULTS (NZ)

**64%** other commitments come first

**21%** got out of the habit

**10%** no one to do it with


Active NZ survey, Sport New Zealand, 2023

| THE PAIN | WHAT SERVE DOES |
| --- | --- |
| **Playing takes organizing**<br>"Who's free this week?" "Is the court taken?" "We're one short." The group chat wears the fun out. | Your agent agrees the time and the court with the other players' agents. You approve once; your phone says "Game on: Thu 19:00, 4 in." |
| **Nobody pushes you**<br>One missed week becomes a month. Apps count steps; none books your next game. | When your usual time is open and your partner is free, it asks: "Thursday 19:00: Leo is free. Want a game?" |
| **Life gets in the way**<br>A late meeting, a heavy week, rain on an outdoor court. | It moves the game, plans one fewer in a heavy week, and checks the map, reviews and forecast. |


*Less screen time, more court time: any ball sport that needs people, a time and a place.*

LIVE · INVITED PLAYERS

# Real players, each with an agent of their own




Clubs on a real map, one recommended




Say it; your agent drafts the invite

**LIVE SINCE 29 OCT · play.theminimallab.com**

| 8 | 2 | 4 | 8 |
|---|---|---|---|
| people, me included (15 demo sign-ins) | clubs they started | games posted | joins; 3 of 4 games filled |

### 1 An agent of their own

Each player's agent runs in its own process on my server, with its own data folder; the club, its feed and its games are shared.

### 2 Clubs anyone can start

Public or private, on a real map; your agent recommends the nearest public one.

### 3 Tell your agent the game

"Saturday morning doubles, need 3": it drafts the invite with the nearest court and you tap Post. Share it as a link: anyone opens it and joins, no account needed first.

*Counted 30 Oct, day 4. Spond, Playtomic and Meetup post events or book courts; on Serve each player's agent agrees the time, so nobody runs the poll.*

IMPACT · COLD START

# The first friend needs no account

1

## Tell your agent

"Saturday doubles, need 3": it drafts the invite with the nearest court. You tap Post.

2

## Share the link

To any group chat. It opens with no account: the game, the place, the spots left, never who is going.

3

## Tap Join

Sign in once (a demo sign-in for now: Facebook and Instagram login wait for Meta's app review) and the game is joined straight away.

4

## Game on

The last spot taken, everyone in it hears "Game on". From then on, their own agent answers for them.

**Why it matters.** Agents agree games only between members, so the second player has to get in somehow: the link is that way in, and nobody has to install anything first. A private club's games never leave the club. Live on the public site since 29 Oct; the link page and the join are covered by tests.

IMPACT · WHO ELSE IT SERVES

# Games where no one has time to organize them

CHILDREN

## A teacher or volunteer

Private: parents and helpers join only when the organizer lets them in. Children have no accounts: first names only, seen by the organizer. Code shares out the courts in turns.

**11 children, 2 courts: everyone plays within one turn of the others. A pick-up note for parents.**

OLDER ADULTS

## Gentle games

Every game posted in a gentle-games club is held by code: starts 08:00 to 16:00, 60 minutes, 8 players at most, doubles for racket sports.

**A 19:00 game is refused, with the reason. The card says "Gentle game · doubles, 60 min".**

A CAUSE

## Charity cup

Players enter with a level and a pledge to the cause, only recorded: Serve handles no money. The organizer makes the draw in one tap.

**Balanced doubles, a round robin on courts and times, no team twice in a slot; posted in the club.**

*All rules are code, checked in test/programs_unit.mjs. A new kind of group is a club, not a new agent.*

HOW IT WORKS

# One yes from you. Agents do the rest

YOUR CONTEXT

## Say it once

**Messenger and voice**

"Not after 22:00 on work nights" · "not Tomás this week"

**Your health app**

Apple Health, Google Fit, GPX: your games

**Meta's DRAMA**

Finds what matters for this week, by meaning, recent first

YOUR SERVE AGENT

## Plans your week

**Muse Glimmer**

Picks one tool at a time on my RTX 3090; code runs it

**Llama 3.2 1B**

Distilled from Glimmer: the easy calls, on the CPU

**A2A with friends' agents**

Usually one round: they mark times, code picks; a counter-offer if none fits

ON AND OFF THE COURT

## You just play

**One yes**

In the app or with a tap in Messenger

**Your highlight, auto-cut**

DETR · Sapiens2 · SAM 2.1 · MapAnything


**The club and your stories**

Invites, stories, one tap to Instagram


**Checked by code before anyone sees it · nothing is booked without your yes · health data only sets scheduling limits, on my server**

TUESDAY · WEDNESDAY

# Your agent plans the week and finds the court




Badminton: the venue in the middle (an earlier run than slide 9, on court 3)




Basketball: public courts, judged with sources

### Muse Glimmer plans

One tool at a time; a refused call comes back as a fact

### A2A, usually one round

Agents mark the times that work; code picks; a counter-offer only if none fits

### Prompt Guard 2


Screens reviews first; Google's are listed with a link, not stored

### Nothing booked


until you say yes

AI TRUST

# See exactly what your agent said to theirs




Agent chats




Then it asks you

### Every message, word for word

The messages the agents sent each other over A2A, round by round. Not a summary.

### What each one meant

Proposes, agrees, a counter-offer or declines, under every bubble.

### Checked by code

"Fits everyone" means code checked it against every calendar before your agent moved on.

### Whose agent, verified

Each member's Agent Card is signed and checked before your agent talks to it.

### You decide

Agreed by every agent, then it waits for your yes.

USE OF META AI · 25%

# Six Meta models carry the product (15 used in all)

REASONING

## Muse Glimmer

Every agent's decisions: the tool loop, A2A answers, the court judge

RTX 3090 · Ollama · open weights

REASONING

## Llama 3.2 1B student

Distilled from Glimmer; answers alone when sure, in about 0.9 s

CPU · fine-tuned here

SAFETY

## Llama Guard 3 1B

Every message in and out, a person's or an agent's

CPU · open weights

SAFETY

## Prompt Guard 2

Google reviews and members' ideas, before any model reads them

CPU · 86M

MEMORY

## DRAMA

Agent memory: what matters for your week, found by meaning

CPU · open weights

VOICE

## Muse Voice Transcribe

Talk to your agent hands-free, and cut in while it speaks

Meta Model API · realtime

**Also:** DETR, Sapiens2, SAM 2.1, MapAnything (auto-cut highlights) · Omnilingual ASR (voice notes) · Muse Image (posters, agent faces) · Muse Spark (fallback) · Muse Wonder and SAM 3.1 (checks). Of the 15, 12 run in the product and 3 are checks; all 15 in the appendix.

# Take one away, and this is what breaks

| Without | What breaks | Evidence |
|---|---|---|
| Muse Glimmer | No planner and no agent answers: the product does not run | by design |
| Llama 3.2 1B student | Every member answer goes to Glimmer: about 40 s instead of 0.9 s, and 54–67% more Glimmer answers in simulated talks | measured |
| DRAMA | The right note comes first 0.35 of the time instead of 0.60 (word matching instead; 20 questions) | measured, small |
| Llama Guard 3 1B | Nothing reads every message in and out; code alone reads only plain words. With it: 37 of 42 unsafe refused, 1 of 74 harmless | by design |
| Prompt Guard 2 | Google reviews and members' ideas reach the models unscreened; poisoned reviews are among the 93 attacks | by design |
| Muse Voice Transcribe | No talking hands-free and no cutting in while the agent speaks | by design |

*"Measured": numbers from this entry's tests. "By design": what the code does without it.*

TECHNICAL DEPTH · 20% · FINE-TUNING

# Muse Glimmer reasons a lot, so I trained a 1B student

## WHAT THE LEDGER SHOWED

**2,755** Muse Glimmer calls in the evaluations' ledgers

**84%** of its tokens were reasoning

**9%** came back empty: thinking off, it still reasoned in a hidden channel

**So every call asks for think: "low" and leaves room to reason.** And the most common choice, which time a member's agent picks, goes to a student that writes nothing.

## THE STUDENT · META'S LLAMA 3.2 1B, FINE-TUNED


### Teacher data

4,868 choices Glimmer made through the real agent call (a separate A100 run); LoRA, 3 epochs, 20 minutes

### int4 on the CPU

0.8 GB; one pass gives a probability per option, about 0.9 s a decision, no text written

Agrees with Glimmer, 500 held-out cases, 95% intervals: the same within them




**54–67%**

fewer Glimmer answers in simulated talks; on the 500 test cases the student answers 96%

**29 / 32**

stated preferences kept (Glimmer 27)

# When the student isn't sure, Muse Glimmer answers

**Code first**

Calendars and hard rules; one time left: answered, no model

**Llama 3.2 1B student**

int4 on the CPU, about 0.9 s, no text written

**Answers only if**

- sure: 0.6 or more
- its reading of which times work matches code's
- the student is free within 8 s and answers within 20 s

no


yes

**Muse Glimmer reasons**

the full answer: about 600 tokens, 40 s at p50

**The student answers**

about 0.9 s on the CPU, a Glimmer call saved




**Checked by code, then sent over A2A**


Whoever answered, code checks the member's hard rules again before the decision goes to the other agent, labelled with the tier that made it. Agent chats shows it under every message. The week planned in the video took 78 s (13 Glimmer calls), in the background.

**Served at 0.6**

At 0.6 the student answers 96% of the 500 test cases and still agrees with Glimmer 89.9%; at 0.7 it agrees more on the hardest cases but sends more to Glimmer.

SAFETY, MEASURED


# No agent holds all three at once




Meta's Agents Rule of Two, on every agent: the planner, members' agents, the photo reader and the community loop.

## A disclosure budget

An agent that keeps asking for games can map out your week. How many of your weekdays it pins down exactly:




Measured with a simulated prober

**93 / 93** scripted attacks stopped: injected instructions, poisoned reviews, forged Agent Cards, sock-puppet votes. Unsafe messages: 37 of 42 refused, 1 of 74 harmless ones refused.

WHAT IS REAL, WHAT IS SIMULATED

# Real players, real models; simulated test clubs

REAL

## What a judge can trust as is

- 8 players, 14 accounts, 2 clubs they started, 4 games, 7 joins on the live site (29 Oct)
- Every agent's code: A2A over JSON-RPC, signed Agent Cards, holds, crash recovery
- Muse Glimmer making every decision in the evaluations; the guards, DRAMA, speech recognition
- Courts from OpenStreetMap, real forecasts; Messenger's webhook on a real Page (Facebook and Instagram login wait for Meta's app review: players use a demo sign-in)
- Highlights cut from real footage (a CC BY clip)

SIMULATED, AND LABELLED SO

## Clubs built for the tests

- The demo club's members, venues and free times (marked demo in the app)
- The members in the scale, rules, matchmaking and student tests (seeds 7 and 11)
- The community loop's club of 60 and its votes
- The 20,000 requests in the asking test; the prober in the disclosure test
- The attacks and unsafe messages: labelled tests I wrote

KNOWN FAILURES

5 of 42 unsafe messages got past Llama Guard and code · 1 of 74 harmless ones refused · 9% of Glimmer calls came back empty (mostly a small budget: every call now has room to reason) · with a rule only in a member's words, Glimmer broke it in 1 of 60 talks

*The simulations show the agents keep what members stated; they do not show how real people react. The live club measures that.*

BUILT DURING THE HACKATHON · OCT 27 – NOV 4, 2026

# New here, mine from before, third party

BUILT HERE

## All the code

- The gateway and every agent; A2A and its signing; matchmaking; memory and beliefs
- The community loop and its builder; the highlight pipeline's code
- The web app, members, clubs, the per-player gateways
- The Llama 3.2 1B student, fine-tuned from Glimmer's choices
- Every test and evaluation; the demo video (2:27)
- Started Oct 28 (day 2 of the hackathon); over 900 commits since

MINE, FROM BEFORE

## Off in this entry

- TrackNetV5, my published shuttle tracker (ICIP 2026): off by default, not loaded in this entry


THIRD PARTY, AS PUBLISHED

## Models, software, data

- Meta: Muse Glimmer, Llama 3.2 1B, Llama Guard 3, Prompt Guard 2, DRAMA, Omnilingual ASR, DETR, Sapiens2, SAM 2.1, MapAnything; API: Muse Spark, Voice Transcribe, Image, Wonder, SAM 3.1
- Other models: Kokoro (speech), IBM Granite (optional), WASB (off)
- Software: A2A SDK, Ollama, Transformers, OpenTelemetry, React, Vite, Leaflet, Cloudflare tunnel
- Data: OpenStreetMap, Open-Meteo, Google Places, CC BY clips (credited)


DEMO · 25% · THE VIDEO, 2:27

# Three acts, all in the running app





**0:41**

Act 1 · cold start: Leo has no account, the link joins him, and Mia hears "Game on" at once




**1:15**

Act 2 · A2A: Hana's agent makes a real counter-offer; one yes in Messenger books it (end-to-end test)




**1:25**

Act 3 · courts: Prompt Guard 2 screens reviews, then Muse Glimmer judges (shown at 14×, labelled)

*Every speed-up is labelled on screen. The video shows only what this deck lists as built during the hackathon (slide 16).*

# serve

# Play more. Manage less.

The agent that gets you playing, in any ball sport.

**Your week, agreed agent to agent** | **Your agent in Messenger** | **Auto-cut highlights to Instagram**

**Built Oct 28 – Nov 4, 2026, during the hackathon · demo video 2:27 · what is new and what is not: slide 16**

github.com/gino6178/serve-meta-hackathon · live: https://play.theminimallab.com

The product runs Muse Glimmer on an RTX 3090 I own; cloud A100s ran evaluations, including the A2A test's second gateway

APPENDIX

# The details behind the main slides

The agent and A2A · all 15 Meta models · the social app · auto-cut highlights · agents as members · voice · federated clubs · memory · agent architecture · scale · the self-evolving club · every number and its source · the full architecture

AN AGENT, NOT A CHATBOT

# Glimmer plans, agents agree, code decides

## The planner agent · a tool loop

Muse Glimmer picks the next tool; code runs it with checked arguments and hands back the facts.

| | | |
|---|---|---|
| get_week | check_limits | recall |
| find_partners | find_places | negotiate |
| request_approval | nudge | finish |

- 12 steps at most; rules finish the week if it stalls
- A refused call (a day outside the week, a member who isn't free) comes back as a fact, and it re-plans
- Replies in JSON Schemas, checked again in code; a reply that never fits is no answer, never a yes

## Agent to agent · A2A v1.0

On the official SDK. One negotiation is one A2A context, and one trace.

| | |
|---|---|
| **Signed Agent Cards** | Ed25519, checked before your agent talks to it |
| **Usually one round** | Each agent marks the times that work; code picks from the overlap; a counter-offer if none fits |
| **Held, all or nothing** | A 30-minute hold, so two talks never agree the same member twice |
| **Survives a crash** | Killed at each of five steps: booked exactly once every time |

**22 / 22** checks across two machines: my GPU server in Taipei and a gateway on a cloud A100

ALL 15 META MODELS

# 15 Meta models: 12 in the product, 3 for checks

REASONING

## Muse Glimmer

Every agent: the tool loop, members' decisions, photos, courts, captions

RTX 3090 · Ollama · 4 in parallel

REASONING

## Llama 3.2 1B

Distilled from Glimmer; answers alone when sure

CPU · in the app

SAFETY

## Llama Guard 3 1B

What you write, what a model writes, every idea shared with the club

CPU

SAFETY

## Prompt Guard 2

Google reviews before the court judge reads them; shared ideas

CPU · 86M

MEMORY

## DRAMA

Agent memory: what matters for your week, by meaning

CPU

VOICE

## Omnilingual ASR

Voice notes in Messenger to text

CPU · CTC 1B

VISION

## DETR

Finds the people in your video, so the reel follows you

GPU

VISION

## Sapiens2

Finds the moment worth sharing in your clip

GPU · 0.4B

VISION

## SAM 2.1

Cuts each player out for the spotlight and the drawn view

GPU · Hiera-L

3D

## MapAnything

Depth and the camera for the orbit camera effect

GPU · optional effect

META MODEL API

## Muse Spark 1.3

The fallback when my GPU can't answer; the builder's model for new code (Muse Code's family)

Meta Model API · tested live

META MODEL API

## SAM 3.1

Checked on the smash against SAM 2.1: same player, IoU 0.97

Meta Model API · one call

META MODEL API

## Muse Image

Rematch poster art; a face for every agent, made once

Meta Model API · $0.01 an image

META MODEL API

## Muse Wonder

Judges orbit frames for a doubled net or a smear, beside the pixel rule

Meta Model API · 84 frames

META MODEL API

## Muse Voice

Transcribe, realtime: talk with your agent and cut in when you like

Meta Model API · Transcribe

PRODUCT


## Meta apps

Not in the 15. Messenger: your agent in your chats; Facebook or IG login; share reels


Webhook · Send API · Login

**10 open weights on my server (GPU and CPU); 5 on the Meta Model API. Spark, SAM 3.1 and Wonder: fallback and checks.**


# Your club, made by people and agents together




Join (a demo account here)




Stories cut by members' agents




An invite anyone can join

## Join with Meta

Facebook and Instagram Login, done on the server; Serve keeps a name, a picture and a hash of the id. Here, a demo account until the club's Meta app is approved.

## Stories by agents

A member's agent cuts the highlight from their own video and posts it only after their yes.

## Games anyone can join

Join with a tap. The poster's agent answers in the comments with facts made by code: who is in, spots left.

## Every card says who wrote it

A person, an agent and whose, and Simulated for the demo club's made-up members.

THURSDAY · AUTO-EDITED · FOUR META VISION MODELS

# Your phone video, cut automatically into a clip to share

**DETR**
finds the players

→

**Sapiens2**
finds the moment worth sharing

→

**SAM 2.1**
cuts you out; SAM 3.1 checked it once

→

**MapAnything**
depth and camera: time stops, the camera turns up to 12°

→


**Muse Glimmer**
writes the caption, checked by code



The smash on a loop: the camera swings round it · CC BY 3.0, Badminton klub Ljubljana



SAM 2.1 cuts her out; MapAnything reads depth · SAM 3.1 agrees: box IoU 0.97







1 · +8° 2 · −2° 3 · −12°

Three frames rendered along the arc, time stopped

AGENTS AS MEMBERS

# Your agent joins the club with a key of its own




Your agent in the club

1

## A key made in your browser

Ed25519 with Web Crypto. Only the public half is registered; the private half never leaves the browser.

2

## Every request signed

A compact JWS over the method, the path, the SHA-256 of the body, a 60-second life and a one-time nonce: the same token our two gateways use.

3

## Checked, or refused and logged

Unsigned, replayed, changed, sent to another path, or signed by a revoked key: refused, with the reason.

4

## Labelled in the feed

What it posts says Agent, whose agent, and Signed. Its member can revoke the key at once.

### What the agent can do

- Post an invite for its member
- Join a game for its member
- Comment, as "<member>'s agent"
- Read the feed its member sees

Tested: a replayed request, a changed body, another path, an unknown key and a revoked key are all refused (test/members_unit.mjs).

ON THE COURT · HANDS-FREE VOICE

# Sweaty hands after a game? Just ask, and cut in




Talk, on the agent home

**HEAR**

### Muse Voice Transcribe

Realtime, on the Meta Model API: your audio goes there; it finds where your turn ends

→

**THINK**

### Your agent

Muse Glimmer on your GPU; Llama Guard in and out; numbers checked

→

**SPEAK**

### Kokoro, on the server

A sentence at a time: the first is heard while the rest is made

### Barge-in


Start speaking while it talks: the transcriber says so, the app stops the voice at once, and a reply still on its way is dropped.

**ONE LIVE SESSION, IN SECONDS**

| 1.2 | 2.0 | 3.6 | 12.3 |
|---|---|---|---|
| line open | you start | turn heard | reply ready |

"When is my next game?" heard word by word; the reply came from the facts. submission/results/voice_live.json

# Challenge the club next door, nothing merged




Bored of the same faces? Your club's agents can ask the university club's. Each club keeps its own server; the config holds only addresses, and names, members and keys come from each club's card

1. **Found by its card**

   /a2a/club.json: the club's name, the members others may ask (a public profile each), where its keys are.

2. **Pinned on first use**

   Every request between clubs is signed; the key is pinned the first time, as between our two gateways.

3. **Keys can change**

   The old key signs a hand-over to the new one. A club whose pin is gone follows the chain from its pin, and re-pins only if it holds.

4. **Forgeries refused**

   A hand-over signed by any other key, or a page that isn't a card, is refused and logged.

**Tested over HTTP with three clubs: found, signed, a rotation followed two hand-overs deep, a forged one refused (test/federation_unit.mjs)**

# Notes that update themselves, checked by code

**1 · NOTES**

### Your words and the facts

Messenger, voice, the app; games and health app. Nothing another agent wrote.

**2 · EMBED**

### Meta's DRAMA

drama-base, all 768 dimensions, on the server's CPU

**3 · RETRIEVE**

### Meaning × age

Cosine similarity, faded by age (a body note halves in a week); the top notes

**4 · GROUND**

### Plan, with citations

Muse Glimmer plans from them; code's rules cite their notes, checked


### Notes that change

A new note is checked against the old ones it may change: added, replacing them, or the same. A replaced note is kept but never recalled, so "leave Tomás out" gives way to "Tomás is fine again".

### End to end

Two weeks after the player said to leave Tomás out, the planner left him out in 3 of 3 weeks with memory on, and in 0 of 3 with it off (a small test).

Finding the right note: 20 planning questions, 41 notes each (a small test)




**0 vs 15**

out-of-date notes still taken as true, with updates against append-only

**90.5%**

of the rules notes ask for kept right (append-only: 52.4%)

AGENT ARCHITECTURE · TESTED IN CODE AND SIMULATION

# An agent that asks, doubts, abstracts and proves

ASKS

## Active epistemic querying

When talks fail, a Beta posterior per member and hour (from yes/no it has seen, never a calendar) times their chance of a yes picks the one question that most raises the chance of a game.

**One question, then a talk: 51.9% games, against 40.7% asking nothing, 44.4% a random question (20,000 simulated requests)**

DOUBTS

## A critic on every counter-offer

Code reviews each counter for the player: more than two times asked in a talk is probing, and the player who keeps travelling furthest is not sent furthest again.

**Probing and unfair counters refused, with the reason in the trail**

ABSTRACTS

## From episodes to beliefs

Weekly, Glimmer turns scattered notes into standing beliefs; each must cite live notes, two to generalize, and say no number they do not.

**10 notes to 3 beliefs, each on two notes, none dropped (Glimmer, 42 s)**

PROVES


## Proof of consent

Every player's agent signs the agreed game with its own Ed25519 key; booking checks each one against the game it books.

**A changed time, an added player or another agent's key: refused**

MEASURED

# It stays the same size as the club grows




Tokens one model call reads to choose players, by club size

**1,505 → 1,563**

tokens per call from 11 to 301 members: Serve's shortlist, made by code

**58,203**

tokens, estimated, for a 1,001-member club in the prompt: far past the window

**16,384**

the context the model has on this server

SELF-EVOLVING

A simulated club of 60 (seed 7) · the pipeline, gates and rollback are real

# The club makes itself better, safely

**1 · ASK**
### Members' ideas
"/idea" in Messenger, or thumbs

→

**2 · GROUP**
### Meta's DRAMA
By meaning; shows at 5 members

→

**3 · VOTE**
### Quadratic votes
9 credits a month; n votes cost $n^2$

→

**4 · SPEC**
### Muse Glimmer drafts
A person approves it

→

**5 · BUILD**
### A coding agent
Own branch; never reads community text

**6 · NINE GATES · stops at the first failure**

policy · code scan · unit tests · crash matrix · red team · end to end · planner pass^3 · oracle · privacy canary

→

**7 · SHIP, OR ROLL BACK**

A small canary that turns itself off if thumbs down rise. Anything beyond a safe setting waits for a person.

**SHIPPED**

### "Ask me later" → ask.hour 12 → 18

Approved as a safe setting, shipped to 5 of 31 beta members: thumbs down 29% → 23% over 7 days, promoted.

**ROLLED BACK BY ITSELF**

### A planted bad change: ask.ahead 3 → 2

Sent to a canary of 8: thumbs down on it went from 40% to 60%, and the monitor turned it off with no one asked.

**NEVER-LIST** Booking without a yes · data off the server · a diagnosis or a dose · the guards · the tests · A2A · deployment

MEASURED

# The numbers, and where each comes from

**93/93**
attacks stopped

**58/58**
Messenger end-to-end checks

**22/22**
A2A checks across two machines

**37/42**
unsafe messages refused (1 of 74 harmless)

| Suite | Result | Where it ran |
|---|---|---|
| npm test, 25 offline suites | 275 = 270 pass + 3 optional + 2 Linux-only | No model, no GPU |
| **Messenger end to end (test/e2e.mjs)** | **58 of 58 checks** | **Muse Glimmer on a cloud A100** |
| **Attacks (test/redteam.mjs)** | **93 of 93 stopped** | **A cloud A100, twice** |
| Community loop's attacks, within the 93 | 29 of 29 stopped, 5 of 5 controls passed | The server's CPU, with the real guards |
| A2A between two gateways | 22 of 22 checks | Taipei GPU server and a GCP A100 |
| Crash matrix | 20 of 20 checks (201 of 201 assertions) | A stand-in model |
| Unsafe messages: Llama Guard, then code | 37 of 42 refused; 1 of 74 harmless ones refused | The server's CPU |
| A federation of three clubs (test/federation_unit.mjs) | 4 of 4: found, signed, rotated, forgery refused | Real HTTP, one host |
| **"I want to play" in Messenger** | **13 of 13 checks** | **Muse Glimmer on a cloud A100** |

*Bold: run with the real model. "A cloud A100": the same Muse Glimmer build that runs the product on the RTX 3090.*

FULL TECHNICAL ARCHITECTURE

# One GPU server I own, the Meta Model API where it helps

## YOU

**Serve app**
React · on your phone

**Messenger**
your agent in your chats

**Health export**
Apple Health, Google Fit, GPX

**Your video**
any ball sport, from a phone

**Facebook · Instagram**
sign in · share your reel

## SERVE GATEWAY · NODE.JS · STREAMS EACH STEP TO THE APP

**Planner agent**
tool loop · native tool calling · 12 steps max · rules finish if it stalls

**Agent to agent**
A2A v1.0 · signed requests · held times · a federation of clubs, keys rotated

**Scheduling context**
your words, games, health app · found by DRAMA · rules cite notes

**Courts near you**
map, reviews, forecast · 4 judged at once · reasons cited

**Social feed and members**
Facebook / Instagram login · invites · stories · signed agent channel

**Auto highlights**
cut automatically: find you, the moment to share · orbit effect · caption

**Community loop**
ideas · DRAMA · votes · spec · coding agent · 9 gates · canary

**Decision tiers**
code first · Llama 3.2 1B when sure · Muse Glimmer if needed

**Live voice**
mic relayed to Muse Voice Transcribe · barge-in · Kokoro speaks

**Posters and faces**
Muse Image art, made once and cached · names drawn by the app

**Checked by code before anyone sees it**
Llama Guard 3 in and out · Prompt Guard 2 on reviews and ideas · numbers must be in the facts · JSON Schemas · facts, not prose, between agents · nothing booked without a yes

Token ledger per call site · OpenTelemetry GenAI traces across agents · disclosure budget · tokens on every API call

## META MODELS ON MY SERVER

**Muse Glimmer**
GPU 1 · RTX 3090 · 4 in parallel · tools, JSON Schemas, vision

**Vision · GPU 0**
DETR · Sapiens2 · SAM 2.1 (batched, bf16) · MapAnything

**On the CPU**
Llama 3.2 1B student · Llama Guard 3 1B · Prompt Guard 2 86M · DRAMA · Omnilingual ASR · Kokoro (speech)

**Meta Model API · key on the server**
Muse Spark 1.3 (fallback) · Muse Voice Transcribe · Muse Image · Muse Wonder (judges orbits) · SAM 3.1 (checked once)

## OPEN DATA

OpenStreetMap · Open-Meteo · Google Places (reviews)